



SECTION

NOTES

1. ALL SAW CUT AND SEALED JOINTS TO BE EITHER PARALLEL WITH, OR PERPENDICULAR TO, THE CENTERLINE OF THE PIPE.
2. ALL MATERIALS ARE TO MEET FORM 816, AS AMENDED
3. IF THERE IS EVIDENCE OF SETTLEMENT OR UNDERMINING AT EDGE OF TRENCH, THE CONTRACTOR SHALL CUT BACK BASE AND SUBBASE AS NEEDED AND REPLACE AND RECOMPACT BASE AND SUBBASE PRIOR TO PAVING

NOT TO SCALE

TOWN OF SOUTH WINDSOR
STANDARD DETAIL

MARCH, 2005

TEMPORARY PAVEMENT PATCHING DETAIL

REVISED:

APPROVED

PUBLIC WORKS DIRECTOR