Cusson Automotive, Inc.

753 John Fitch Boulevard South Windsor, CT Map 46 Lot 33



SITE LOCUS
1"=1,000"

Applicant

Cusson Enterprises LLC
29 Mascolo Road
South Windsor, CT 06074
(860) 289-2389

Owner


5 DS LLC c/o Barbara A. Dalene East Hartland, CT 06027

Prepared By



DRAWING INDEX

SHEET TITLE	SHEET NO.	LATEST REVISION
CIVIL COVER SHEET KEY MAP BOUNDARY PLAN EXISTING CONDITIONS & DEMOLITION PLAN LAYOUT & LANDSCAPE PLAN GRADING & EROSION CONTROL PLAN UTILITY PLAN CONSTRUCTION NOTES & DETAILS DETAILS DETAILS	·1 of 11 ·2 of 11 ·3 of 11 ·4 of 11 ·5 of 11 ·6 of 11 ·7 of 11 ·8 of 11 ·9 of 11	5-22-23 5-22-23 5-22-23 5-22-23 5-22-23 5-22-23 5-22-23 5-22-23 5-22-23 5-22-23
DETAILS		5-22-23



TTC

BY: LF/TAC CHK: JEU Automotive,

REVISIONS


Key Map


Cusson


<u>DATE</u> 5-22-23 SCALE 1"=100'


JOB NUMBER 2023-014 SHEET


2 of 11











Site Preparation

established.

Grade in accordance with the Land Grading measure which is in the Connecticut Guidelines For Soil Erosion and Sediment Control latest edition.

and to provide erosion protection until the seeding becomes

Install all necessary surface water controls.

For areas to be mowed remove all surface stones 2 inches or larger. Remove all other debris such as wire, cable tree roots, pieces of concrete, clods, lumps, or other unsuitable material.

<u>Seed Selection</u> Lawn Areas: Premium Seed Mix for Sun and Shade.

Stormwater Basin & Slopes: New England Erosion Control/Restoration Mix by New England Wetland Plants, Inc. or approved equal.

Apply topsoil, if necessary, in accordance with the Topsoiling measure which is in the Connecticut Guidelines For Soil Erosion and Sediment Control latest edition.

Apply ground limestone and fertilizer according to soil test recommendations (such as those offered by the University of Connecticut Soil Testing Laboratory or other reliable source).

Where soil testing is not feasible on small or variable sites, or where timing is critical, fertilizer may be applied at the rate of 300 pounds per acre or 7.5 pounds per 1,000 square feet of 10-10-10 or equivalent and limestone at 4 tons per acre or 200 pounds per 1,000 square feet.

Work lime and fertilizer into the soil to a depth of 3 to 4 inches with a disc or other suitable equipment.

Inspect seedbed just before seeding. If the soil is compacted, crusted or hardened, scarify the area prior to seeding.

Seed Application

Apply selected seed at rates per manufacturer's recommendations uniformly by hand, cyclone seeder, drill, cultipacker type seeder or hydroseeder (slurry including seed, fertilizer). Normal seeding depth is from 0.25 to 0.5 inch. Increase seeding rates by 10% when hydroseeding or frost crack seeding. Seed warm season grasses during the spring period only.

Mulchin

See guidelines in the Mulch For Seed measures.

MAINTENANCE

Inspect temporary soil protection area at least once a week and within 24 hours of the end of a storm with a rainfall amount of 0.5 inch or greater during the first growing season.

Where seed has been moved or where soil erosion has occurred, determine the cause of the failure and repair as needed.

TEMPORARY SEEDING (TS)

SPECIFICATIONS

Site Preparation

Install needed erosion control measures such as diversions, grade stabilization structures, sedimentation basins and grassed waterways in accordance with the approved plan.

Grade according to plans and allow for the use of appropriate equipment for seedbed preparation, seeding, mulch application and mulch anchoring.

Seedbed Preparation

Loosen the soil to a depth of 3-4 inches with a slightly roughened surface. If the area has been recently loosened or disturbed, no further roughening is required. Soil preparation can be accomplished by tracking with a bulldozer, discing harrowing, raking or dragging with a section of chain link fence.

Apply ground limestone and fertilizer according to soil test recommendations (such as those offered by the University of Connecticut Soil Testing Laboratory or other reliable source).

If soil testing is not feasible on small or variable sites, or where timing is critical, fertilizer may be applied at the rate of 300 pounds per acre or 7.5 pounds per 1,000 square feet of 10-10-10 or equivalent.

Apply seed uniformly by hand, cyclone seeder, drill, cultipacker type seeder or hydroseeder. The temporary seed shall be Rye (grain) applied at a rate of 120 pounds per acre. Increase seeding rates by 10% when hydroseeding.

_____ See guidelines in the Mulch For Seed measures.

Mulahina

MAINTENANCE

INAINTENANCE
Inspect temporary seeding area at least once a week and within 24 hours of the end of a storm with a rainfall amount of 0.5 inch or greater for seed and mulch movement and rill erosion.

Where seed has been moved or where soil erosion has occurred, determine the cause of the failure and repair as needed.

MULCH FOR SEED (MS)

SPECIFICATIONS

Types of Mulches within this specification include, but are not

1. Hay: The dried stems and leafy parts of plants cut and harvested, such as alfalfa, clovers, other forage legumes and the finer stemmed, leafy grasses. The average stem length should not be less than 4 inches. Hay that can be windblown should be anchored to hold it in place.

2. Straw: Cut and dried stems of herbaceous plants, such as wheat, barley, cereal rye, or brome. The average stem length should not be less than 4 inches. Straw that can be windblown should be anchored to hold it in place.

3. Cellulose Fiber: Fiber origin is either virgin wood, post-industrial/pre-consumer wood or post consumer wood complying with materials specification (collectively referred to as "wood fiber"), newspaper, kraft paper, cardboard (collectively referred to as "paper fiber") or a combination of wood and paper fiber. Paper fiber, in particular, shall not contain boron, which inhibits seed germination. The cellulose fiber must be manufactured in such a manner that after the addition to and agitation in slurry tanks with water, the fibers in the slurry become uniformly suspended to form a homogeneous product. Subsequent to hydraulic spraying on the ground, the mulch shall allow for the absorption and percolation of moisture and shall not form a tough crust such that it interferes with seed germination or growth. Generally applied with tackifier and fertilizer. Refer to manufacturer's specifications for application rates needed to attain 80%-95% coverage without interfering with seed germination or plant growth. Not recommended as a mulch for use when seeding occurs outside of the recommended seeding dates.

Tackifiers within this specification include, but are not limited to: Water soluble materials that cause mulch particles to adhere to one another, generally consisting of either a natural vegetable gum blended with gelling and hardening agents or a blend of hydrophilic polymers, resins, viscosifiers, sticking aids and gums. Good for areas intended to be mowed. Cellulose fiber mulch may be applied as a tackifier to other mulches, provided the application is sufficient to cause the other mulches to adhere to one another. Emulsified asphalts are specifically prohibited for use as tackifiers due to their potential for causing water pollution following its application.

Nettings within this specification include, but are not limited to: Prefabricated openwork fabrics made of cellulose cords, ropes, threads, or biodegradable synthetic material that is woven, knotted or molded in such a manner that it holds mulch in place until vegetation growth is sufficient to stabilize the soil. Generally used in areas where no mowing is planned.

Site Preparation

Grade according to plans and allow for the use of appropriate equipment for seedbed preparation, seeding, mulch application and mulch anchoring.

Application

Timing: Applied immediately following seeding. Some cellulose fiber may be applied with seed to assist in marking where seed has been sprayed, but expect to apply a second application of cellulose fiber to meet the requirements of Mulch For Seed in the Connecticut Guidelines For Soil Erosion and Sediment Control

Spreading: Mulch material shall be spread uniformly by hand or machine resulting in 80%—95% coverage of the disturbed soil when seeding within the recommended seeding dates. Applications that are uneven can result in excessive mulch smothering the germinating seeds. For hay or straw anticipate an application rate of 2 tons per acre. For cellulose fiber follow manufacture's recommended application rates to provided 80%—95% coverage.

When seeding outside the recommended seeding dates, increase mulch application rate to provide between 95%—100% coverage of the disturbed soil. For hay or straw anticipate an application rate to 2.5 to 3 tons per acre.

When spreading hay mulch by hand, divide the area to be mulched into approximately 1,000 square feet and place 1.5—2 bales of hay in each section to facilitate uniform distribution.

For cellulose fiber mulch, expect several spray passes to attain adequate coverage, to eliminate shadowing, and to avoid slippage.

Anchoring: Expect the need for mulch anchoring along the shoulders of actively traveled roads, hill tops and long open slopes not protected by wind breaks.

When using netting, the most critical aspect is to ensure that the netting maintains substantial contact with the underlying mulch and the mulch, in turn, maintains continuos contact with the soil surface. Without such contact, the material is useless and erosion can be expected to occur.


MAINTENANCE Inspect mulch for


Inspect mulch for seed area at least once a week and within 24 hours of the end of a storm with a rainfall amount of 0.5 inch or greater until the grass has germinated to determine maintenance needs.

Where mulch has been moved or where soil erosion has occurred, determine the cause of the failure and repair as

SOIL ERSOION & SEDIMENT CONTROL NOTES


- 1. The contractor/developer shall notify the Town Staff prior to construction in accordance with the local approvals and permits.
- All soil erosion and sediment control work shall be done in strict accordance with the Connecticut Guidelines For Soil Erosion and Sediment Control latest edition.
- 3. Any additional erosion/sediment control deemed necessary by the engineer during construction, shall be installed by the developer. In addition, the developer shall be responsible for the repair/replacement and/or maintenance of all erosion control measures until all disturbed areas are stabilized to the satisfaction of the town staff.
- 4. All soil erosion and sediment control operations shall be in place prior to any grading operations and installation of proposed structures or utilities and shall be left in place until construction is completed and/or area is stabilized.
- 5. In all areas, removal of trees, bushes and other vegetation as well as disturbance of the soil is to be kept to an absolute minimum while allowing proper development of the site. During construction, expose as small an area of soil as possible for as short a time as possible.
- 6. The developer shall practice effective dust control per the soil conservation service handbook during construction and until all areas are stabilized or surface treated. The developer shall be responsible for the cleaning of nearby streets of any debris from these construction activities
- 7. All fill areas shall be compacted sufficiently for their intended purpose and as required to reduce slipping, erosion or excess saturation. Fill intended to support buildings, structures, conduits, etc., shall be compacted in accordance with local requirements or codes.
- 8. Topsoil is to be stripped and stockpiled in amounts necessary to complete finished grading of all exposed areas requiring topsoil. The stockpiled topsoil is to be located as designated on the plans. Topsoil shall not be placed while in a frozen or muddy condition, when the subgrade is excessively wet, or in a condition that may otherwise be detrimental to proper grading or proposed sodding or seeding.
- 9. Any and all fill material is to be free of brush, rubbish, timber, logs vegetative matter and stumps in amounts that will be detrimental to constructing stable fills. Maximum side slopes of exposed surfaces of earth to be 3:1 or as otherwise specified by local authorities.
- 10. Soil stabilization should be completed within 5 days of clearing or inactivity in construction.
- 11. Waste Materials All waste materials (including wastewater) shall be disposed of in accordance with local, state and federal law. Litter shall be picked up at the end of each work day.
- 12. The Contractor shall maintain on—site additional erosion control materials as a contingency in the event of a failure or when required to shore up existing BMPs. At a minimum, the on—site contingency materials should include 30 feet of silt fence and 5 straw haybales with 10 stakes.





SOURCE: U.S. DEPARTMENT OF AGRICULTURE, SOIL CONSERVATION SERVICE, STORRS, CONNECTICUT


GEOTEXTILE SILT FENCE (GSF)




NOTE:
SILT SACK SHALL BE SIZED TO FIT EACH INLET GRATE (SINGLE OR DOUBLE) AND SHALL BE CLEANED AND MAINTAINED UNTIL THE CONTRIBUTING WATERSHED IS STABILIZED WITH VEGETATION AND/OR COMPACTED PROCESSED STONE BASE.

CB INLET PROTECTION (SILT SACK)

NOT TO SCALE



ANTI-TRACKING PAD DETAIL (CE)



NOTE: MAY BE USED AS ALTERNATIVE TO GEOTEXTILE SILT FENCE.

PERIMETER SEDIMENT BARRIER

CHECKLIST FOR EROSION CONTROL PLAN

PROJECT: Cusson Automotive

LOCATION: 753 John Fitch Boulevard, South Windsor, CT

PROJECT DESCRIPTION: Construction of an automotive repair facility

PARCEL AREA: 9.92 acres

RESPONSIBLE PERSONNEL: Jim Aldrich (860) 647-7544 ext. 101

EROSION AND SEDIMENT CONTROL PLAN PREPARER: J.R. Russo & Associates, LLC

CHECKLIST:

entrance pla	s shown on lan.		
entrance pla			
Install parimeter			
F	s shown on lan.		
Install inlet protection at CBs	s installed		

MAINTENANCE OF MEASURES:						
Location	Description or Number	Date	Initials			

Project Dates:

Date of groundbreaking for project

<u>Date of final stabilization:</u>

PROJECT NARRATIVE AND CONSTRUCTION SEQUENCE

This project is located at 753 John Fitch Boulevard in South Windsor, Connecticut. The proposed activity is the construction of a 12,000 square foot automobile repair facility with the potential for a 5,250 square foot addition to be constructed in the future. The suggested schedule of construction is as follows:

- 1. Install construction anti-tracking pad (CE).
- . Install sediment barriers (GSF) at project perimeters.
- 3. Clear and grub trees and shrubs to be removed. All wood debris and stumps are to be disposed of off—site.
- 4. Strip topsoil. Stockpile suitable amount of topsoil for reuse on—site in areas shown. Stockpiles shall be surrounded by sediment barriers (GSF).
- 5. Rough grade area surrounding proposed building.
- 6. Begin building construction.
 7. Construct stormwater management basin and install drainage. Seed basin as soon as
- practicable.
 8. Install other site utilities.
- 9. Install gravel storage area, parking lot and driveway base.
- 10. Install dumpster pad and sidewalks.
- 11. Pave binder course.12. Stabilize disturbed areas to receive topsoil and permanently seed as soon as possible.
- 13. Install landscaping.

 14. Install pavement top course in all areas. Sweep binder course and apply tack coat prior to
- placing pavement top course. 15. Apply paint striping.

16. Remove sediment barriers after site is fully stabilized.

Construction of this site is anticipated to begin in the fall of 2023 and be complete in the spring of 2024. Temporary erosion control measures shall be installed prior to any soil disturbance and maintained throughout construction until soils have been stabilized with permanent vegetation.

The Contractor shall keep the area of disturbance to a minimum and establish vegetative cover on exposed soils as soon as practical. All soil and erosion control measures shall be installed and maintained in accordance with these plans and the "Connecticut DEEP Guidelines for Soil Erosion and Sediment Control", as amended. The Contractor shall verify all conditions noted on the plans and shall immediately notify the Engineer of any discrepancies.

The developer shall be responsible for the repair/replacement/maintenance of all erosion control measures until all disturbed areas are stabilized. Accumulated sediment shall be removed as required to keep silt fence functional. In all cases, deposits shall be removed when the accumulated sediment has reached one—half above the ground height of the silt fence. This material is to be spread and stabilized in areas not subject to erosion, or to be used in areas which are not to be paved or built on. Silt fence (GSF) is to be replaced as necessary to maintain proper filtering action. Silt fence (GSF) are to remain in place and shall be maintained to insure efficient sediment capture until all areas above the erosion checks are stabilized and vegetation has been established.

POST CONSTRUCTION MAINTENANCE NOTES:

The property owner shall be responsible for performing the following post construction maintenance schedule:

- 1. Maintain lawn & landscape areas with minimal pesticides.
- Sweep parking lot and paved areas at least once per year in the spring.
 Inspect catch basins and storm manholes at least twice per year, including after sweeping.
 Clean at least once per year in April and as necessary to prevent the discharge of pollutants from structures. Remove accumulated oil, trash and excessive sediment with vac—truck. Check condition of hoods (if applicable).
- 4. Inspect infiltration basins annually for evidence of hydrocarbons and remove by vac—truck. Repair eroded areas and replace riprap and vegetation as required. Dredge bottom of forebay to remove accumulated sediment every 10 years or when significant volume reduction is observed. Mow infiltration basin on a regular basis to maintain as lawn area for filtering of pollutants. Inspect inlet pipes monthly and remove trash and debris as needed.

Ses LLC
Substitute
Substitute

on Enterprises LLC 29 Mascolo Road th Windsor, CT 06074 (860) 289—2389

Cusson Enter

29 Mascol

South Windsor,

REVISIONS

BY: LF/TAC CHK: JEU

 $totive,\ Inc.$ Boulevard

Son Automotive
753 John Fitch Boulev
outh Windsor, Connect
Map 46 Lot 33

Erosion &
Sediment Control

Notes

DATE
5-29-23
SCALE
AS SHOWN


JOB NUMBER
2023-014
SHEET

8 of 11


S:\Acad\2023 Civil 3D\2023-014 Cusson Automotive - 29 Mascolo Rd\Russo Drawings\2023-0

NOTE: WHERE SUBGRADES ARE ON WET SILT OR CLAY, CONTRACTOR TO INSTALL ADDITIONAL 12" OF 3/4" CRUSHED STONE ON TENSAR TRIAX GEOGRID BELOW GRAVEL SUBBASE.


PAVEMENT DETAIL NOT TO SCALE



BITUMINOUS CONCRETE LIP CURBING NOT TO SCALE



GRAVEL SURFACE DETAIL




- NOTES:

 1. EXPANSION JOINTS TO BE PLACED AT MAXIMUM 20' SPACING AND BETWEEN ADJACENT SLABS, AT BUILDING LINE, AT CURBS, OR AT PENETRATING STRUCTURES. USE 1/2" PREFORMED EXPANSION JOINT M.03.01-5, SET 1/4" BELOW SURFACE AND SEAL GAP WITH ELASTOMERIC POLYURETHANE JOINT
- 2. TRANSVERSE FALSE JOINTS AT MAX. 5' INTERVALS. NO LONGITUDINAL JOINTS.
- 3. CONCRETE SHALL MEET CTDOT CLASS "F" STANDARDS.
- 4. SIDEWALK TO RECEIVE BROOM FINISH TO MATCH EXISTING.


TYPICAL SIDEWALK DETAIL

NOT TO SCALE




NOTE: TO BE USED ALONG ACCESS DRIVE TO MAINTENANCE BUILDING WITHIN ELECTRICAL EASEMENT.

CAPE-COD STYLE CURB




SIDEWALK RAMP TYPE B




INTEGRAL SIDEWALK & CURB DETAIL

NOT TO SCALE

NOTE: FINISH PER TYPICAL SIDEWALK DETAIL




<u>PLAN</u>



SECTION A-A

CONC. DUMPSTER PAD DETAIL NOT TO SCALE



POLE MOUNTED EXTERIOR LIGHT

NOT TO SCALE

RUSSSOFONGINEERS
SERVING CT & MA
J.R. Russo & Associates, LLC
PO Box 938, 1 Shoham Rd East Windsor, CT 06088
www.jrrusso.com·CT 860,623,0569·MA 413.785.1158

Cusson Enterprises LLC
29 Mascolo Road
South Windsor, CT 06074
(860) 289—2389

REVISIONS
BY: LF/TAC CHK: JEU


Automotive, Inc. winder Coppetion

Cusson Automc753 John Fitch ESouth Windsor, Co

Details

DATE
5-29-23
SCALE
AS SHOWN
JOB NUMBER
2023-014

9 of 11



- NOTES:


 1. MINIMUM COVER OVER TOP OF PIPE SHALL BE 2'-0".

 2. WALL THICKNESS SHALL BE SUFFICIENT TO MEET HS 20 LOADING.


 3. WALL THICKNESS FOR STRUCTURES OVER 10' HIGH IS 12" FOR CONCRETE BLOCK UNITS, INSIDE DIMENSIONS REMAIN THE SAME.

 4. ALL PIPES SHALL BE CUT FLUSH WITH INSIDE WALLS.


 5. ALL BRICKS SHALL BE CONCRETE.
- TYPE "C" CATCH BASIN NOT TO SCALE




SHRUB PLANTING NOT TO SCALE




TREE PLANTING NOT TO SCALE




HDPE STORM DRAIN DETAIL NOT TO SCALE




NYROPLAST ENVIROHOOD DETAIL NOT TO SCALE





OUTLET STRUCTURE NOT TO SCALE



Details

REVISIONS

BY: LF/TAC CHK: JEU

Automotive


Cusson


<u>DATE</u> 5-29-23 <u>SCALE</u> AS SHOWN JOB NUMBER 2023-014

> SHEET 10 of 11

MODIFIED RIPRAP APRON (12" THICK) ON 6" GRANULAR BASE (M.02.01) ON MIRAFI 140N FABRIC OR EQUAL TYPE A RIPRAP APRON (OP) N.T.S.


NOT TO SCALE







PRECAST CONCRETE MANHOLE

NOT TO SCALE





INSIDE DROP DETAIL NOT TO SCALE



PROVIDE WARNING TAPE, 12-24" ABOVE TOP OF PIPE.
 BACKFILL SHALL BE SUITABLE NATIVE MATERIAL UNLESS DETERMINED TO BE UNSUITABLE BY THE ENGINEER OR GRANULAR FILL M.02.01 PLACED AND COMPACTED

IN 12" LOOSE LIFTS. 3. UNDER PAVED AREAS COMPACT BACKFILL TO 95% OF THE MATERIAL'S MAXIMUM DRY DENSITY AS DETERMINED BY A STANDARD PROCTOR TEST. UNDER UNPAVED AREAS COMPACT TO 90%.

4. UNSUITABLE TRENCH MATERIAL TO BE REMOVED AND REPLACED WITH 3/4" CRUSHED STONE AS DIRECTED BY ENGINEER.

TYPICAL SANITARY SEWER TRENCH SECTION

NOT TO SCALE

REVISIONS BY: LF/TAC CHK: JEU Automotive,Boule

> Details <u>DATE</u>

Cusson

5-29-23 <u>SCALE</u> AS SHOWN JOB NUMBER 2023-014

SHEET 11 of 11